# Soft X-ray FEL beamline

SACLA Users' Meeting 2017

Shigeki Owada On behalf of SACLA



#### Introduction

- Design & Performance
- User operation
- > Beamline upgrades
  - Arrival timing monitor
  - Sub-µm focusing system
  - Future plan

### Introduction

- > Design & Performance
- User operation
- > Beamline upgrades
  - Arrival timing monitor
  - Sub-µm focusing system
  - Future plan

### **Utilization of soft X-ray at SACLA**

#### SACLA started user operation in Jun. 2012



More research opportunities in softer X-ray region



**Relocation & re-employment of the SCSS** 

### SCSS (Sering-8 Compact SASE Source)

- SACLA prototype machine R&D for the compact FEL Utilization of FEL
- Milestone
  - 2005 Construction & commissioning
  - 2006 First lasing
  - 2007~ User operation
  - 2012~ User operation at SACLA
  - 2013 Decommissioned



HHG-seeded FEL, T. Togashi, et al., Opt. Express, 19, 317, (2011).



	SACLA	SCSS	Ratio
E-beam energy	8 GeV	250 MeV	32:1
Length	700 m	< 60 m	11:1
Accelerator units	64	2	32:1
No. of Undulators	18	2	9:1
Photon energy	4 - 15 keV	20 - 24 eV	< 700:1 <sub>5</sub>

#### Introduction

### > Design & Performance

#### User operation

#### > Beamline upgrades

- Arrival timing monitor
- Sub-µm focusing system
- Future plan

# Light source

Relocation of the SCSS to the SACLA undulator hall



Upgrade of the SCSS (SCSS+)

**E-beam energy :** ~ 250 MeV **Photon energy :** ~ 20 eV



SCSS (~2013)

**2015 Oct.** ~ ~ 500 MeV first lasing ~ 37 eV **2016 Aug. ~** ▲ ~ 800 MeV





### **Photon beamline**

#### **Distance from light source**



### **Operation status**





### **Operation parameters**

	BL1 (SXFEL)						
E-beam							
Energy	250 MeV < 800 MeV		5 ~ 8 GeV				
Charge	~ 0.3 nC ~ 0.3 nC ~ 0.3 nC		~ 0.3 nC				
Rep. rate	20 Hz	60 Hz	30 Hz (60 Hz)				
Undulators							
Total length	9 m	14 m	106 m				
Periodic length	15 mm	5 mm 18 mm 18 mm					
K value	< 1.5 < 2.1 < 2.1		< 2.1				
FEL							
Photon energy	20 ~ 25 eV	40 ~ 150 eV	4 ~ 15 keV				
Pulse energy	10 ~ 30 μJ/pulse~ 80 μJ/pulse (@ 100 eV)~ 600 μJ/pulse (@ 10 keV)		~ 600 µJ/pulse (@ 10 keV)				
Pulse duration		a few hundred fs	< 8 fs 10				

### **Gain curve measurement**



### Estimation of 3rd harmonics at 100 eV

- > Pulse energy vs. Gas attenuator ( $N_2$ ) pressure
- 3rd harmonics contribution is estimated at 100 eV



### Introduction

#### > Design & Performance

### User operation

#### > Beamline upgrades

- Arrival timing monitor
- Sub-µm focusing system
- Future plan

### **User operation**

- ✤ User operation: Jul. 2016 ~
- Beamtime : 5 ~ 7 shifts (1 shift = 12h)
- ✤ 6 ~ 7 proposals / half year



#### Introduction

- > Design & Performance
- User operation
- > Beamline upgrades
  - Arrival timing monitor
  - Sub-µm focusing system
  - Future plan

### **Arrival timing measurement at BL1**

- Reflectivity change combined with spatial encoding Small penetration depth of GaAs (< 30 nm @100 eV)</p>
- > 1D focusing for enhancing efficiency
  - ~ 5  $\mu$ J/pulse, 70  $\mu$ m (H) × 3300  $\mu$ m (V), FWHM
  - => fluence = ~ 3 mJ/cm<sup>2</sup> << damage threshold



### Results



# **Arrival timing monitor**

Wavefront-splitting for beam branching

- Elliptical mirror for 1D focusing (f = 1300 mm)
- Branching ratio : < 10 %</li>
- Installation & Commissioning : 2018 May~



Arrival timing monitor (2018 Jun. ~)

### **Beamline upgrade**

Plane mirror with 1.5 deg glancing angle

- Beam axis : Horizontal
- Beam height : 1505 mm => 1220 mm (@focus position)
- ✤ Installation : Aug. 2018 ~



# Sub-1µm focusing system



#### Using KB mirrors...

Beam size become smaller = Mirror length become shorter

Light source position = KB focus position

### **Results**

#### Spot size measured by knife-edge scan



<u>Peak intensity : ~1 × 10<sup>17</sup> W/cm<sup>2</sup> (80 µJ, ~100 fs)</u>

### **Perspectives**

C-band accelerator units for higher energy

E-beam e	energy : ~	0.8 GeV	<b></b> < ~ 1.7	GeV	
Photon e	nergy : ~ 100	eV @K=2.1	<b>V</b> < ~ 470	eV @K=2	2.1
Gun Booste Buncher S-	r -band accelerator C-band ac	celerator C-band accele	rator		
	■·■·■				
Chopper	Bunch compressor	Bunch compressor Extra space	e for additional	Undulator accelerator	units Beam dump

- Polarization control (helical undulator, etc.)
- Soft X-ray/Hard X-ray pump-probe experiment SCSS+ linac is synchronized to SACLA main linac

### Summary

- The SCSS was re-employed and upgraded. (~100 µJ @ 100 eV)
- ➢ We started user operation from Jun. 2016.
- We will continue facility upgrades and beamline development.

### Thank you for your attention